BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division

Schedule - B

NAME OF THE WORK: Construction of SWM wall at survey no. 93 Mallasandra in ward no. 13 in Dasarahalli sub division

Description of work	Unit	Qty	Rate quoted by the contractor by sri Gnanedra Murthy M D	
			In Figures (Rs.)	In Words (Rs.)
2	3	4	5	6
1	Earthwork excavation by manual means in hard soil including an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	389.4	105.0	Rupees One Hundred Five Only
2	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 kgs, using 40mm and down size graded granite metal coarse aggregates @ 0.86cum and fine aggregate @ 0.45cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	97.35	4691.0	Rupees Four Thousand Six Hundred Ninety One Only
3	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chisele dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	623.04	4653.0	Rupees Four Thousand Six Hundred Fifty Three Only
4	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .6cum, with super plasticisers @ 3 liters confirming to is 9103: 1999 reaffirmed 2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	93.46	5588.0	Rupees Five Thousand Five Hundred Eighty Eight Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

5	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per the direction of Engineer-in-charge of the work	Cum	389.4	65.0	Rupees Si Five Onl

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner